

The successful bidder agrees to be substantially complete with all work within **210** calendar days of the Notice to Proceed and achieve final completion within 30 calendar days after issuance of the Certificate of Substantial Completion including punch list items.

In the event the successful bidder fails to achieve Substantial Completion or Final Completion of the project within the time limits specified or extended time limits as agreed upon, liquidated damages shall be paid to the OWNER or deducted from amounts due the Contractor, at the rate of Six Hundred Dollars (\$600.00) per calendar day until Substantial Completion is achieved, and/or until Final Completion is achieved. Sundays and legal holidays shall be excluded in determining the number of days in default.

BID SCHEDULE – AUBURN FARMS PARK:

ITEM	SPEC	DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL
Part 00200 - Temporary Features and Appurtenances						
1	0210	Mobilization	L.S.	1		
2	0221	Temporary Work Zone Traffic Control, Complete	L.S.	1		
3	0280	Erosion Control	L.S.	1		
4	0280	Construction Entrance, Type 1	Each	1		
5	0280	Concrete Washout Facility	Each	1		
6	0280	Inlet Protection, Type 3	Each	8		
Part 00300 - Roadwork						
7	0305	Construction Survey Work	L.S.	1		
8	0310	Asphalt Pavement Sawcutting	L.F.	210		
9	0320	Clearing and Grubbing	L.S.	1		
10	0330	General Excavation	C.Y.	5,390		
11	0331	12 Inch Subgrade Stabilization	S.Y.	120		
Part 00400 - Drainage and Sewers						
12	0415	Mainline Video Inspection	L.F.	795		
13	0430	4 Inch Drain Pipe	L.F.	215		
14	0430	12 Inch ADS AdvanEdge Flat Pipe	L.F.	420		
15	0445	4 Inch PVC Storm Sewer Pipe	L.F.	14		

16	0445	6 Inch PVC Storm Sewer Pipe	L.F.	45		
17	0445	8 Inch PVC Storm Sewer Pipe	L.F.	476		
18	0445	4 Inch PVC Sanitary Sewer Pipe	L.F.	48		
19	0445	6 Inch PVC Sanitary Sewer Pipe	L.F.	226		
20	0470	Storm Sewer Cleanout	Each	5		
21	0470	Catch Basin	Each	2		
22	0470	Catch Basin, Beehive Inlet	Each	4		
23	0470	Concrete Manhole, 48" Drywell	Each	1		
24	0470	NDS Flo-Well Drywell	Each	1		
25	0470	Sanitary Sewer Cleanout	Each	5		
26	0470	Catch Basin, Splash Pad Area Drain	Each	1		
27	0490	Adjusting Boxes	Each	1		
28	0490	Connection to Existing Structures	Each	1		
Part 00600 - Bases						
29	0640	Aggregate Base	TON	1,210		
Part 00700 - Wearing Surfaces						
30	0744	Level 2, 1/2" ACP Mixture	TON	290		
31	0749	Asphalt Walks	S.F.	13,147		
32	0759	Concrete Curb, Standard Vertical Curb	L.F.	981		
33	0759	Concrete Curb, Monolithic Curb & Gutter	L.F.	170		
34	0759	Concrete Curb, Modified Mountable Curb	L.F.	20		
35	0759	Concrete Driveways, Reinforced	S.F.	504		
36	0759	Concrete Walks	S.F.	18,147		
37	0759	Extra for New Curb Ramps	Each	2		
38	0759	Truncated Domes on New Surfaces	S.F.	28		

Part 00800 - Permanent Traffic Safety and Guidance Devices						
39	0815	Removable Bollards	Each	2		
40	0860	Longitudinal Pavement Markings - Paint	L.F.	421		
41	0867	Pavement Legend, Type E: Disabled Parking	Each	2		
42	0867	Pavement Legend, Type E: "NO PARKING"	Each	1		
43	0869	Curb Marking, Paint	L.F.	170		
Part 00900 - Permanent Traffic Control and Illumination Systems						
44	0905	Remove and Reinstall Existing Signs	L.S.	1		
45	0930	Perforated Steel Square Tube Anchor Sign Supports	L.S.	1		
46	0940	Signs, Standard Sheeting, Sheet Aluminum	S.F.	14		
47	0960	Site Electrical System, Complete	L.S.	1		
Part 01000 - Right of Way Development and Control						
48	1030	Permanent Seeding	Acre	0.15		
49	1030	Water Quality Seeding	Acre	0.04		
50	1030	Lawn Seeding	Acre	0.78		
51	1040	Topsoil	C.Y.	1,140		
52	1040	Deciduous Trees, 1.5" Cal.	Each	42		
53	1040	Shrubs and Groundcover, 5 Gal.	Each	211		
54	1040	Shrubs and Groundcover, 1 Gal.	Each	611		
55	1040	Groundcover, 4" Pots	Each	345		
56	1040	Bark Mulch	C.Y.	88		
57	1050	CL-6 Black Vinyl Coated Chain Link Fence with Privacy Slats	L.F.	1,376		
58	1050	4 Foot x 72 Inch Chain Link Single Gates	Each	1		
59	1095	Benches	Each	13		
60	1095	Picnic Tables	Each	15		

61	1095	Refuse Receptacles	Each	8		
62	1095	Bicycle Racks	Each	3		
63	1095	Gazebo	Each	3		
64	1095	Pet Waste Station	Each	2		
65	1095	Drinking Fountain	Each	2		
66	1095	Prefabricated Restroom	Each	1		
67	1095	Splash Pad	L.S.	1		
68	1095	Basketball Court	L.S.	1		
69	1095	Synthetic Turf Surfacing - Pad	S.F.	9,376		
70	1095	Synthetic Turf Surfacing - No Pad	S.F.	224		
71	1095	Playground Equipment	L.S.	1		
72	1095	Soccer Goal	L.S.	1		
73	1095	Precast Concrete Wheelstop	Each	10		
Part 01100 - Water Supply Systems						
74	1120	Irrigation System	L.S.	1		
75	1140	3/4 Inch Potable Water Pipe, Fittings and Couplings with Class A Backfill	L.F.	407		
76	1140	2 Inch Potable Water Pipe, Fittings and Couplings with Class B Backfill	L.F.	113		
77	1150	2 Inch Double Check Valve Backflow Prevention Assembly	Each	1		
78	1170	2 Inch Water Service Connection Piping	L.F.	38		
TOTAL						

Accompanying herewith is Bid Security, which is equal to five percent (5%) of the total amount of the Basic Bid.